

AD-A156 533


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BAKER FLOODWATER RESE. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV JUL 79


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A


AD-A156 533

MERRIMACK RIVER BASIN
WENTWORTH, NEW HAMPSHIRE

**BAKER FLOODWATER RESERVOIR
SITE 11A
NH 00247**

NHWRB NO. 249.14

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**



**DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154**

DTIC FILE COPY

JULY 1979

85 06 14 013

DEPARTMENT A
Approved for public release
Distribution Unlimited

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00247	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Baker Floodwater Reservoir Site 11A NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE July 1979
		13. NUMBER OF PAGES 76
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin, Wentworth, New Hampshire, Tributary to Baker River.		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a 640 ft. long, 24 ft. high earthen structure. The visual inspection revealed that the dam is in good condition. The inspections also revealed random surface cracks and scaling of the concrete on the riser structure. It is small in size with a high hazard potential classification. There are no recommendations resulting from the inspection.		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:
NEDED

DEC 06 1979

Honorable Hugh J. Gallen
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Dear Governor Gallen:

Inclosed is a copy of the Baker Floodwater Reservoir Site 11A Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire and the owner of the dam.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely,

MAX B. SCHEIDER
Colonel, Corps of Engineers
Division Engineer

Incl
As stated

BAKER FLOODWATER RESERVOIR SITE 11A

NH 00247

NHWRB 249.14

MERRIMACK RIVER BASIN
WENTWORTH, NEW HAMPSHIRE

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

Accession For		
NTIS GRA&I		<input checked="" type="checkbox"/>
DTIC TAB		<input type="checkbox"/>
Unannounced		<input type="checkbox"/>
Justification		
By		
Distribution/		
Availability Codes		
Dist	Avail and/or Special	
A/1	23	24



NATIONAL DAM INSPECTION PROGRAM
PHASE I - INSPECTION REPORT
BRIEF ASSESSMENT

Identification No.: NH00247
Name of Dam: Baker Floodwater Reservoir Site 11A
Town: Wentworth
County and State: Grafton, New Hampshire
Stream: Tributary to Baker River
Date of Inspection: May 16, 1979


Baker Floodwater Reservoir Site 11A is a 640 foot long 24 foot high earthen structure. There is one fill zone in the dam which includes a cutoff wall. Top width of the dam is 12 feet. The upstream and downstream embankments are on a 3 horizontal to 1 vertical slope. Appurtenant structures consist of a principal spillway, plunge pool stilling basin and emergency spillway. The principal spillway has two inlets, a low stage orifice and a high stage covered top spillway. The inlets discharge through the riser to a 2.5 foot diameter concrete pipe. The reservoir can be drained by a 12 inch diameter gated pipe. The dam construction was completed in November of 1971. Plans, design calculations and construction data were prepared by the Soil Conservation Service and are available for inspection.

The visual inspection revealed that the dam is in good condition. The visual inspection revealed random surface cracks and scaling of the concrete on the riser structure and a fallen tree in the channel downstream of the dam.

Based on the small size of the dam and its high hazard classification and in accordance with Corps of Engineers guidelines, the test flood inflow should be between 1/2 the Probable Maximum Flood (PMF) and the full PMF. A test flood inflow equal to 1/2 the PMF, which is equal to 1,580 cfs, was used. The routed test flood outflow of 670 cfs does not overtop the dam. With the water level at the top of the dam, the spillways will pass the routed test flood outflow. The hydraulic design calculations indicate that the principal spillway was designed for a 100 year frequency flood. The crest elevation of the dam was designed using a watershed runoff depth of 5.81 inches.

There are no recommendations resulting from the Phase I Inspection. Remedial measures include the establishment of a downstream warning system in the event of emergency, the removal of a fallen tree in the downstream channel, and repair of the cracks and scaling of concrete on the riser structure.


The remedial measures are described in Section 7 and should be completed within two (2) years of the receipt of this report by the owner.





Gordon H. Slaney, Jr.
Gordon H. Slaney, Jr., P.E.
Project Engineer

Howard, Needles, Tammen & Bergendoff
Boston, Massachusetts


This Phase I Inspection Report on Baker Floodwater Reservoir Site 11A has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.


JOSEPH W. FINEGAN, JR., MEMBER
Water Control Branch
Engineering Division


CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division


JOSEPH A. MCELROY, CHAIRMAN
Chief, NED Materials Testing Lab.
Foundations & Materials Branch
Engineering Division

APPROVAL RECOMMENDED:


JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii-iv
Overview Photo	v
Location Map	vi

REPORT

1. PROJECT INFORMATION	1-1
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
1.2 Description of Project	1-1
a. Location	1-1
b. Description of Dam and Appurtenances	1-2
c. Size Classification	1-2
d. Hazard Classification	1-2
e. Ownership	1-2
f. Operator	1-2
g. Purpose of Dam	1-3
h. Design and Construction History	1-3
i. Normal Operational Procedure	1-3
1.3 Pertinent Data	1-3
2. ENGINEERING DATA	2-1
2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	3-1
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-2
d. Reservoir Area	3-3
e. Downstream Channel	3-3
3.2 Evaluation	3-3
4. OPERATIONAL PROCEDURES	4-1
4.1 Procedures	4-1
4.2 Maintenance of Dam	4-1
4.3 Maintenance of Operating Facilities	4-1
4.4 Description of any Warning System in Effect	4-1
4.5 Evaluation	4-1
5. HYDRAULIC/HYDROLOGY	5-1
5.1 Evaluation of Features	5-1
a. General	5-1
b. Design Data	5-1
c. Experience Data	5-1
d. Visual Observation	5-1
e. Overtopping Potential	5-1
f. Dam Failure Analysis	5-1
6. STRUCTURAL STABILITY	6-1
6.1 Evaluation of Structural Stability	6-1
a. Visual Observation	6-1
b. Design and Construction Data	6-1
c. Operating Records	6-1
d. Post-Construction Changes	6-1
e. Seismic Stability	6-1

<u>Section</u>	<u>Page</u>
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	7-1
7.1 Dam Assessment	7-1
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1
d. Need for Additional Investigation	7-1
7.2 Recommendations	7-1
7.3 Remedial Measures	7-1
7.4 Alternatives	7-2

APPENDIXES

APPENDIX A - INSPECTION CHECKLIST

APPENDIX B - ENGINEERING DATA


APPENDIX C - PHOTOGRAPHS

APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS

APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL
INVENTORY OF DAMS



BAKER RIVER DAM - SITE 11A - Overview looking upstream



NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
BAKER FLOODWATER RESERVOIR SITE 11A

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Howard, Needles, Tammen & Bergendoff has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire, Authorization and notice to proceed were issued to Howard, Needles, Tammen & Bergendoff under a letter of March 30, 1979 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0060 has been assigned by the Corps of Engineers for this work.

b. Purpose.

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of dams.

1.2 Description of Project

a. Location. Baker Floodwater Reservoir Site 11A (Baker Dam Site 11A) is located on a tributary to the Baker River approximately 0.5 miles upstream of Buffalo Road in the Town of Wentworth, New Hampshire. The Dam is shown on U.S.G.S. Quadrangle Wentworth, New Hampshire, with approximate coordinates N43°-50'-54", W71°-53'-30", Grafton County, New Hampshire. The location of Baker Dam Site 11A is shown on the preceding page.

b. Description of Dam and Appurtenances. Baker Dam Site 11A is an earthen embankment structure. Total length of the dam, according to existing drawings, is 640 feet. Maximum structural height is 35 feet with a 24 foot height from top of dam to the stream bed. According to the plans, there is one fill zone in the structure, which includes a cutoff wall. Top width of the dam is 12 feet and the embankment is on a 3 horizontal to 1 vertical slope both up and downstream.

Appurtenant structures consist of a concrete riser and pipe principal spillway with a covered top inlet. There are two stages to the inlet structure, a low stage orifice and a high stage covered inlet. The riser discharges through a 2.5 foot diameter concrete pipe and a plunge pool type stilling basin. The emergency spillway is located on the right side of the dam and has a width of 140 feet. It is an excavated earthen structure with a vegetative cover. A 12 inch diameter pond drain pipe can be opened from the riser structure to lower the water level. There is a 12 inch diameter gate valve at the riser. A "WYE" fitting on the pond drain pipe, which is ungated, discharges to the low stage trash rack to serve as a secondary approach channel to the low stage intake.

Figures 1 and 2, located in Appendix B, show a plan of the dam and appurtenant structures. Photographs of each structure are shown in Appendix C.

c. Size Classification. Small (hydraulic height - 24 feet, storage - 355 acre-feet) classification based on height being less than 40 feet and storage being less than 1,000 acre-feet as given in Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. The potential for hazard posed by this dam is classified as high. Failure of this dam at maximum pool elevation (top of dam) would result in an average flood wave about 17 feet high through the reach studied, for 1.1 miles downstream of the dam. Four dwellings in the reach would be flooded, and the bridge at Buffalo Road would be overtopped.

e. Ownership. This dam is owned by the New Hampshire Water Resources Board, 37 Pleasant Street, Concord, New Hampshire.

f. Operator. This dam is maintained and operated by the New Hampshire Water Resources Board. Chairman of the Water Resources Board is Mr. George McGee, Sr.; Mr. Vernon Knowlton is Chief Engineer, Telephone No. 603/271-1110.

g. Purpose of Dam. This dam is used for floodwater control. The normal pool is maintained by the low stage intake in the riser. The storage between the low stage outlet and the emergency spillway crest is used for floodwater control.

h. Design and Construction History. The construction of this dam was completed in November of 1971. Design and construction inspection of this dam were done by the Soil Conservation Service, Durham, New Hampshire. The construction contractor was Robie Construction Company, Inc.

i. Normal Operating Procedures. The normal pool is maintained by the low stage inlet on the riser. Under flood conditions, when the capacity of the low stage orifice is exceeded, the storage is utilized. The high stage outlet will reach maximum design discharge before the reservoir reaches the crest of the emergency spillway. The dam does not require any manual operation in order to function.

1.3 Pertinent Data

a. Drainage Area. The area tributary to Baker Site 11A consists of 1.05 square miles of mountainous terrain. There is no development in the watershed except for a road and several dwellings. Maximum elevation is about 2,060 feet, MSL, and the crest of the dam is at elevation 681.5.

The area around the reservoir is mostly wooded. There are no cottages or dwellings along the shoreline. A roadway passes to the right of the reservoir area. The pool area is swamp with many stumps and dead trees.

b. Discharge of Dam Site.

(1) Outlet works for Baker Dam Site 11A consist of an emergency spillway, a riser with a low stage orifice and a high stage covered top spillway, and a 12 inch pond drain pipe controlled by a gate. Invert of the pond drain is at 659.18 feet, MSL. Maximum discharge of the pipe when the reservoir is at the normal pool level of 663.5 feet is about 9 cfs. The low stage orifice has two openings 6 inches by 7 inches in size set at invert 663.5. Capacity of the low stage inlet when the reservoir is at the crest of the high stage inlet (676.76) is 11 cfs. The high stage covered inlet crest set at elevation 676.76 has a capacity of 97 cfs when the water level is at the emergency spillway crest of 678.5. The 140 foot wide emergency spillway has a crest of elevation 678.5 when the water surface is at the top of dam (elevation 681.5) the spillway will have a capacity of 1,169 cfs.

(2) There are no records available of maximum discharge at the site.

(3) The spillway and riser capacity with the water surface at the top of the dam is approximately 1,275 cfs at elevation 681.5.

(4) Spillway and riser capacity with the water surface elevation at the test flood elevation of 680.5 feet is approximately 670 cfs.

(5) The total project discharge at the test flood elevation of 680.5 feet is 670 cfs.

c. Elevation (feet above MSL)

- (1) Streambed at centerline of dam - 657.5
- (2) Maximum tailwater - unknown
- (3) Upstream portal invert pond drain - 659.18
- (4) Normal pool - 663.5
- (5) Full flood control pool - 678.4
- (6) Spillway crest (riser crest) - 676.76 (emergency spillway) - 678.5.
- (7) Design surcharge - 678.4
- (8) Top Dam - 681.5
- (9) Test Flood Surcharge - 680.5.

d. Reservoir (miles)

- (1) Length of Maximum Pool - .77
- (2) Length of Normal Pool - .14
- (3) Length of Flood Control Pool - .74

e. Storage (gross acre-foot)

- (1) Normal Pool - 9.3
- (2) Flood Control Pool - 232
- (3) Emergency Spillway Crest Pool - 238
- (4) Top of Dam - 355

f. Reservoir Surface (acres)

- (1) Normal Pool - 4
- (2) Flood Control Pool - 31
- (3) Spillway Crest - 33
- (4) Test Flood Pool - 37
- (5) Top Dam - 37

g. Dam

- (1) Type - earth
- (2) Length - 640 feet
- (3) Height - 24 feet hydraulic
35 feet structural
- (4) Top Width - 12 feet
- (5) Side Slopes - upstream and downstream 3 horizontal
to 1 vertical
- (6) Zoning - one fill zone
- (7) Impervious core - none
- (8) Cutoff - zone 1 fill
- (9) Grout Curtain - none
- (10) Other - none

h. Diversion and Regulating Tunnel

See Section j

i. Principal Spillway

- (1) Type - concrete riser, covered top
- (2) Length of Weir - total 15 feet
- (3) Crest Elevation - 676.76
- (4) Gates - outlet pipe 2.5 feet diameter
- (5) U/S Channel - none

Emergency Spillway

- (1) Type - earth
- (2) Length of Weir - 140 feet wide
- (3) Crest Elevation - 678.5
- (4) Gates - none
- (5) U/S Channel - Approach channel from reservoir is 140 feet wide with $2\frac{1}{4}$ to 1 side slopes
- (6) Downstream Channel - Below the outlet structure for a distance of 150 feet the channel has grass lined banks, and a rip-rapped channel. Downstream of this section the channel enters a wooded area. Within the wooded area there are many large fallen trees in the channel.

j. Regulating Outlets. The normal level of the reservoir is controlled by two 7 inch by 6 inch orifice inlets set in the riser at invert elevation 663.5. There is a trash rack for each opening but no control gates. The 12 inch pond drain pipe set at invert 659.18 extends 17 feet into the reservoir from the riser, and has a trash rack at the intake. The pipe is controlled at the riser by a 12 inch diameter gate valve. A "wye" connection on the pond drain pipe discharges to the low stage trash rack and functions as a secondary low stage inlet.

SECTION 2 ENGINEERING DATA

2.1 Design

A complete set of design data including layout, hydraulic design, foundation and embankment design, geology and soils reports, structural design, quantities and specifications are available for Baker Dam Site 11A. In addition, there are construction drawings available. Design of the dam was done by the Soil Conservation Service, Durham, New Hampshire.

2.2 Construction

The dam construction was completed in November of 1971. A complete record of construction documents were made available. These documents include: as-built plans, job diaries surveying records, test drilling logs, compaction test results, concrete tests and certificate of completion. Construction was by Robie Construction Co., Inc. and was inspected by the Soil Conservation Service, Durham, New Hampshire.

2.3 Operation

Normally, the pond drain line gate is closed. The normal level of 663.5 feet is maintained by the low stage orifice openings. The principal spillway riser and reservoir storage is designed to retard runoff from up to a 100 year frequency storm without discharge occurring in the emergency spillway (Crest 673.5).

2.4 Evaluation

a. Availability. Engineering data available for Baker Dam Site 11A consists of the information outlined in Sections 2.1 and 2.2. The plans, design data, and construction records are available at the offices of the Soil Conservation Service, Federal Building, Durham, New Hampshire 03824.

b. Adequacy. A complete set of design and construction data did allow for a definitive review within the confines of this Phase I - Inspection Report. Therefore, the adequacy of this dam is based on the design and construction data reviewed, visual inspection, past performance history and sound engineering judgement.

c. Validity. The field inspection indicated that the external features of Baker Dam Site 11A substantially agree with those shown on the available plans.

SECTION 3 VISUAL INSPECTION

3.1 Findings

a. General. The field inspection of Baker Dam Site 11A was made on May 16, 1979. The inspection team consisted of personnel from Howard, Needles, Tammen & Bergendoff and Geotechnical Engineers, Inc. Inspection checklists, completed during the inspection, are included in Appendix A. At the time of inspection, the water level was approximately 1.0 foot above the invert of the low stage inlet. The upstream face of the dam could only be inspected above this water level.

b. Dam. Visual inspection of the dam indicated that it is in good condition.

The dam consists of an earth embankment about 640 feet long and 24 feet high. The embankment is a homogeneous fill of silty fine to medium sand with a cutoff trench extending to rock or an impervious silty till. There is a trench drain along the downstream toe.

There is an unpaved emergency spillway cut into the right abutment passing around the embankment.

A principal spillway consisting of an intake structure, concrete conduit and riprap stilling basin is located near the left abutment.

Upstream Slope. The upstream slope is 3 horizontal to 1 vertical and has a 10-foot-wide berm at approximately 16 feet below the crest. At the time of inspection, the pool was slightly below the level of the berm.

The upstream slope has a good grass cover, as shown in Photo No. 2.

Crest. The crest of dam is 12 feet wide and is grass covered, as shown in Photo No. 4. No significant misalignment of the crest was observed.

Downstream Slope. The downstream slope is 3 horizontal to 1 vertical. The slope, shown in Photo No. 3, is grass covered and in good condition.

There is a riprap-lined gutter at the juncture of the downstream slope and the left abutment, which discharges into the outlet works stilling basin.

The trench drain beneath the downstream toe discharges into a riprap-lined pool at the outlet end of the principal spillway. The 12-inch diameter drainpipes were clear and unobstructed.

c. Appurtenant Structures. Visual inspection of the concrete riser principal spillway structure, auxiliary earth spillway and outlet works structure did not reveal any evidence of stability problems with respect to sliding and overturning. The concrete riser structure generally appeared to be in good condition except for some concrete staining, minor random cracks and surface scaling. The principal spillway trash racks are in good condition.

The concrete riser structure consists of three functional elements; a principal spillway with low and high stage inlets, a vertical transition and a closed discharge conduit. The riser structure is located in the embankment.

Field inspection revealed that the riser structure appeared to be in good condition except for rust and water staining, surface scaling, and random surface cracks, see Photos No. 7, 8, 9. The trash racks for the low and high stage intakes consist of standard shape angles and grating. Both trash racks assemblies are in good condition.

The principal spillway structure has a riprap-lined approach channel which parallels the upstream toe. The portion of the riprap which could be observed is shown in Photo No. 6 and is in good condition.

The pond drain inlet structure, pipe and gate were under water at the time of inspection. The gate control mechanism located on the top of the riser appeared to be in good operational order.

The 2.5 foot diameter principal spillway discharge pipe and concrete support bedding shown in Photos. No. 13 and 14 appeared to be in good condition. The portion of the riprap above the level of the plunge pool shown in Photo No. 12 appears to be in good condition.

The emergency spillway is about 140 feet wide and clear of obstructions with the exception of some low brush. Photos No. 15 and 16 show the emergency spillway upstream and downstream from the dam axis.

d. Reservoir Area. The area around the reservoir is mostly wooded. There are no cottages or dwellings along the shoreline. A roadway (Buffalo Road) passes along the right shore of the reservoir area. The pool area is swamp with many stumps and dead trees.

e. Downstream Channel. Below the outlet structure and plunge pool the channel is riprapped with grassed banks for a distance of about 150 feet. Downstream of this section the channel enters a wooded area. Just into this portion, there is a large fallen tree in the channel. Photo No. 11 shows a portion of the channel. With the exception of minor cattail growth, the channel is in good condition.

3.2 Evaluation

Visual examination indicates the dam is in good condition. The inspection of the dam revealed the following:

(a) The riser structure has some surface sealing, and random surface cracks.

(b) A large fallen tree in the downstream channel.

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedure

Baker Dam Site 11A is used for floodwater control. Under normal operating procedures the normal pool level is maintained by the low stage orifice opening in the riser. Flood events up to a 100 year frequency are retarded by the reservoir storage between the normal pool and the emergency spillway crest. The emergency spillway is utilized only with events greater than a 100 year frequency.

4.2 Maintenance of Dam

The dam is inspected on an annual basis by the New Hampshire Water Resources Board and the Soil Conservation Service. Maintenance is undertaken as a result of the inspection on an as needed basis. The dam is visited on a regular basis (approximately monthly) by representatives of the owner to perform regular maintenance

4.3 Maintenance of Operating Facilities

Maintenance of the outlet works is performed as in Section 4.2.

4.4 Description of Warning Systems

There are no warning systems in effect for this facility.

4.5 Evaluation

The current operation and maintenance procedure for this facility appear to be adequate to insure that any problems encountered can be remedied within a reasonable period of time. However, the owner should establish a warning system to follow in the event of flood flow conditions or imminent dam failure.

SECTION 5
HYDROLOGY AND HYDRAULIC ANALYSIS

5.1 Evaluation of Features

a. General. Baker Dam Site 11A is an earthen embankment dam 640 feet long with a hydraulic height of 24 feet. The dam is constructed with one fill zone and a earth fill core. Appurtenant works consist of a two stage riser and a 2.5 foot diameter concrete pipe which discharges to a plunge pool type stilling basin. An emergency spillway 140 feet wide is located on the left side of the dam. There is a 12 inch diameter gated pond drain pipe which discharges to the riser structure.

The dam is used for floodwater control. The dam is classified as small in size having a height of 24 feet and maximum storage of 355 acre-feet.

b. Design Data. According to the Soil Conservation Service design data, this dam is constructed to retard flood flows of up to a 100 year frequency storm without utilizing the emergency spillway. The design flood control elevation is 678.4 feet or 0.1 feet below the emergency spillway crest. Total runoff for this condition is 3.14 inches during a six hour Type IIB storm. The crest elevation of the dam was designed using a watershed runoff depth of 5.81 inches. The structure is classified as having a "B" hazard which is defined as "being located in a predominately rural and agricultural area, where failure may cause damage to isolated homes, main highways or major railroads or cause interruption of use or service of relatively important public utilities."

c. Experience Data. There are no records available of maximum discharge at the dam site.

d. Visual Observations. No evidence of damage to any portion of the project from overtopping was visible at the time of inspection.

e. Test Flood Analysis. Detailed design data is available for this dam, and the basic conditions are noted above in Paragraph b. The hydrologic evaluation was preformed using information gathered by field investigation, watershed characteristics and Probable Maximum Flood (PMF) guide curves prepared by the Corps of Engineers. In accordance with Corps of Engineers guidelines, the high hazard classification and small size of the dam warrent a test flood magnitude ranging from 1/2 the Probable Maximum Flood to the full PMF. A test

flood of 1/2 the PMF was used as the hazard classification is on the lower end of the range with four buildings affected. A test flood inflow of 1,580 cfs is based on a drainage area of 1.05 square miles in mountainous terrain.

The routed test flood outflow was determined in accordance with Corps of Engineers guidance for Estimating Effect of Surcharge Storage on Maximum Probable Discharge and the hydraulic characteristics of the dam. Discharge through both the primary spillway and emergency spillway was considered. The routing was started with the water surface at the normal pool elevation. The routed test flood outflow was determined to be approximately 670 cfs. As the maximum capacity of the spillways is 1,274 cfs there will be a freeboard of 1.0 feet.

f. Dam Failure Analysis. The impact of failure of the dam was assessed using the "Rule of Thumb" Guidance for Estimating Downstream Dam Failure Hydrographs prepared by the Corps of Engineers. The breach discharge was estimated with the water surface at the crest of the dam and a breach width equal to 40 percent of the total length of the dam. The downstream hydrograph is a sum of the breach discharge and the maximum spillway capacity. Prior to the breach of dam, the downstream river stage would be about 4.5 feet the spillways at a full capacity of 1,274 cfs. Breach of dam would result in an additional 50,600 cfs for a total of about 51,900 cfs. The downstream flood stage was estimated through three reaches for a total distance of 1.3 miles from the dam to the Baker River. The flood wave would be about 20.8 feet high at the dam and 14.1 feet at the Baker River. Four dwellings along this reach would be affected. Two dwellings would be flooded by about 6 feet and the other two would be flooded by about 3 feet. In addition, a shack will be totally inundated and a bridge at Buffalo Road will be overtopped by about 11 feet.

SECTION 6
STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations. The visual inspection of Baker Dam Site 11A did not disclose any immediate stability problems.

b. Design and Construction Data. Design drawings and construction specifications exist and indicate the dam is a homogeneous embankment composed of silty fine to medium sand. The dam has a cutoff trench extending to bedrock on an impervious silty till. There is a trench drain along the downstream toe which extends up both abutments.

An emergency spillway cut into the right abutment passes around the embankment.

A review of the construction data available indicates that the dam and appurtenant structures were constructed according to the plans and specifications.

c. Operating Records. There are no operating records available for this facility.

d. Post-Construction Changes. There is no record of post-construction changes.

e. Seismic Stability. The dam is located in Seismic Zone 2 and in accordance with the recommended Phase I guidelines does not warrant seismic analysis.

SECTION 7
ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual inspection of Baker Flood-water Reservoir Site 11A indicated the dam is in good condition.

(1) Random surface cracks and scaling of concrete on the riser structure.

(2) A fallen tree across the channel downstream of the dam.

The hydraulic analysis reveals that the spillways can pass the routed test flood without overtopping the dam.

b. Adequacy of Information. A complete set of design and construction data did allow for a definitive review with the confines of this Phase I - Inspection Report. Therefore, the adequacy of this dam is based on the design and construction data review, visual inspection, past performance history and sound engineering judgement.

c. Urgency. This dam is in generally good condition. The remedial measures described in Section 7.3 should be accomplished within 2 years of the receipt of this Phase I-Inspection Report by the owner.

d. Necessity of Additional Investigation. No additional investigation is needed to complete the Phase I Inspection.

7.2 Recommendations

There are no recommendations resulting from the Phase I Inspection.

7.3 Remedial Measures

(a) Devise a warning system to follow in the event of emergency conditions.

(b) Remove the fallen tree from the downstream channel.

(c) Repair surface cracks and scaling on the riser structure.

(d) Establish a system such that the reservoir level can be monitored during periods of intense rainfall.

(e) The periodic inspection should be continued on no less than a biennial frequency.

7.4 Alternatives

There are no practical alternatives to the remedial measures described in Section 7.3.

APPENDIX A
INSPECTION CHECKLIST

VISUAL INSPECTION CHECK LIST
PARTY ORGANIZATION

A - 1

PROJECT Site 11A, Baker Dam

DATE May 16, 1979

TIME 2:30 PM

WEATHER Fair

W.S. ELEV. 664.5 U.S. - DN.S

PARTY:

- | | |
|--------------------------|-----------|
| 1. <u>G. Slaney HNTR</u> | 6. _____ |
| 2. <u>S. Mazur HNTR</u> | 7. _____ |
| 3. <u>D. LaGatta GEI</u> | 8. _____ |
| 4. <u>C. Osgood GEI</u> | 9. _____ |
| 5. _____ | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Dam</u>	<u>D. LaGatta , C. Osgood</u>	
2. <u>Spillway, Outlet Works</u>	<u>S. Mazur</u>	
3. <u>and Downstream Channel</u>	<u>G. Slaney</u>	
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

PERIODIC INSPECTION CHECK LIST

A - 2

PROJECT BAKER SITE NO. 11A DAM DATE May 16, 1979PROJECT FEATURE Earth Embankment NAME D. P. LaGattaDISCIPLINE Geotechnical Engineer NAME C. E. Osgood

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	681.5
Current Pool Elevation	664.5
Maximum Impoundment to Date	Unknown.
Surface Cracks	None observed.
Pavement Condition	No pavement.
Movement or Settlement of Crest	None observed.
Lateral Movement	None observed.
Vertical Alignment	No misalignment observed.
Horizontal Alignment	No misalignment observed.
Condition at Abutment and at Concrete Structures	Good.
Indications of Movement of Structural Items on Slopes	No structural items.
Trespassing on Slopes	No evidence of trespassing.
Sloughing or Erosion of Slopes or Abutments	None observed.
Rock Slope Protection - Riprap Failures	No failure observed in gutter or at outlet works.
Unusual Movement or Cracking at or near Toes	None observed.
Unusual Embankment or Downstream Seepage	None. Water level low.
Piping or Boils	None observed.
Foundation Drainage Features	Left and right 12" drainpipe exits are unobstructed.
Toe Drains	None.
Instrumentation System	None.
Vegetation	Grass Covered.

PERIODIC INSPECTION CHECK LIST

A - 3

PROJECT Site 11A, Baker DamDATE May 16, 1979PROJECT FEATURE Intake Channel/StructureNAME D. LaGatta, C. OsgoodDISCIPLINE Geotechnical/StructuralNAME S. Mazur

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots</p>	<p>Riprap is in good condition as observable.</p> <p>Not observable.</p> <p>None.</p> <p>None.</p> <p>Some debris at low trash rack.</p> <p>Galvanized trash rack and concrete surface of riser structure at high and low stages of inlets are in good condition. Bottom water release structure was under water.</p>

PERIODIC INSPECTION CHECK LIST

A - 4

PROJECT Site 11A, Baker Dam DATE May 16, 1979
PROJECT FEATURE Control Tower NAME G. Slaney
DISCIPLINE Structural/Hydraulic/Eng. NAME S. Mazur

AREA EVALUATED

CONDITION

OUTLET WORKS - CONTROL TOWER

a. Concrete and Structural

General Condition

Condition of Joints

Spalling

Visible Reinforcing

Rusting or Staining of Concrete

Any Seepage or Efflorescence

Joint Alignment

Unusual Seepage or Leaks in Gate
Chamber

Cracks

Rusting or Corrosion of Steel

b. Mechanical and Electrical

Air Vents

Float Wells

Crane Hoist

Elevator

Hydraulic System

Service Gates

Emergency Gates

Lightning Protection System

Emergency Power System

Wiring and Lighting System

Bottom water release structure (pond drain) consists of inlet structure and 12" ID cast iron pipe extended to riser structure. Pond drain structure and control gate were under water.

Mechanically operated gate and control mechanism are housed in riser tower structure. Gate is operated from roof of riser structure. Gate and control mechanism appear to be in good operational condition.

PERIODIC INSPECTION CHECK LIST

A - 5

PROJECT Site 11A, Baker Dam DATE May 16, 1979PROJECT FEATURE Spillway/Outlet Works Conduit NAME G. SlaneyDISCIPLINE Structural/Hydraulic NAME S. Mazur

AREA EVALUATED

CONDITION

OUTLET WORKS - TRANSITION AND CONDUIT

General Condition of Concrete

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths

At the time of inspection, outlet works conduits were under water. Riser discharge channel consists of 30" reinforced concrete pipe which is placed on concrete bedding. Discharge conduit appears to be in good condition.

PERIODIC INSPECTION CHECK LIST

A - 6

PROJECT Site 11A, Baker Dam DATE May 16, 1979
PROJECT FEATURE Outlet Structure/Channel NAME D. LaGatta, C. Osgood
DISCIPLINE Structural/Hydraulic/Geotechnical NAME S. Mazur, G. Slaney

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	Concrete outlet pipe and concrete support bedding are in good condition.
Rust or Staining	Some water staining.
Spalling	None
Erosion or Cavitation	Some erosion at end of supporting bedding
Visible Reinforcing	None.
Any Seepage or Efflorescence	None.
Condition at Joints	Good.
Drain Holes	None.
Channel	Riprap for 30 feet from outlet.
Loose Rock or Trees Overhanging Channel	None.
Condition of Discharge Channel	Clear to edge of woods 150 feet from outlet.

PERIODIC INSPECTION CHECK LIST

PROJECT Site 11A, Baker Dam DATE May 16, 1979
 PROJECT FEATURE Outlet Works/Spillway NAME D. LaGatta, C. Osgood
 DISCIPLINE Structural/Hydraulic/Geotechnical NAME S. Mazur, G. Slaney

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u></p> <p>a. Approach Channel</p> <p>General Condition</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Approach Channel</p> <p>b. Weir and Training Walls</p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Any Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Drain Holes</p> <p>c. Discharge Channel</p> <p>General Condition</p> <p>Loose Rock Overhanging Channel</p> <p>Trees Overhanging Channel</p> <p>Floor of Channel</p> <p>Other Obstructions</p>	<p>Grass covered.</p> <p>None.</p> <p>None.</p> <p>Grass covered.</p> <p>This facility has two spillway structures; concrete riser with two inlets and auxiliary earth spillway located at right abutment. Both spillways are in good condition.</p> <p>Water stain.</p> <p>Some surface scaling.</p> <p>None.</p> <p>None.</p> <p>None.</p> <p>Good, grass covered.</p> <p>None.</p> <p>None.</p> <p>Grass covered.</p> <p>None.</p>

PERIODIC INSPECTION CHECK LIST

PROJECT Site 11A, Baker Dam DATE May 16, 1979PROJECT FEATURE Service Bridge NAME _____

DISCIPLINE _____ NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - SERVICE BRIDGE

a. Super Structure

Bearings

Anchor Bolts

Bridge Seat

Longitudinal Members

Under Side of Deck

Secondary Bracing

Deck

Drainage System

Railings

Expansion Joints

Paint

b. Abutment & Piers

General Condition of Concrete

Alignment of Abutment

Approach to Bridge

Condition of Seat & Backwall

This facility has no service bridge.

APPENDIX B
ENGINEERING DATA

1. LIST OF DESIGN, CONSTRUCTION AND MAINTENANCE RECORDS
2. PAST INSPECTION REPORTS
3. PLAN AND DETAILS

AVAILABLE ENGINEERING DATA

1. A set of drawings (25 sheets), dated November 1970 showing plans and details of the dam and appurtenant structures.
 2. Design Data: including layout, hydraulic design, geology and soils reports, structural design, quantities and specifications.
 3. Construction Data: including as-built plans, job diarys, surveying records, test drilling logs, compaction test results, concrete tests and certificate of completion.
- All of the above are on file with the U.S.D.A. Soil Conservation Service, Federal Building, Durham, New Hampshire 03824.

PAST INSPECTION REPORTS

State of New Hampshire

WATER RESOURCES BOARD

37 Pleasant Street
Concord, N.H. 03301

TELEPHONE 281-3300

September 18, 1978

Mr. Keith MacPherson
Soil Conservation Service
Federal Building
Durham, New Hampshire 03824

Dear Mr. MacPherson:

This letter is to inform you of the prevailing conditions at two of the Baker River System Flood Control Sites.

Site No. 6

- 1- Trash racks have been cleared of debris.
- 2- All bushes and tree sprouts on the dam have been pulled, cut or sprayed.
- 3- The concrete is still spalled in several areas of the channel wall and has broken away from the railing posts. The Board feels that it is your agency's responsibility for this repair.
- 4- To date we have not received your agency's recommendation of corrective action regarding the ponding against the right bank channel wall for our review. During this year's inspection this item was of some concern to Ray Winner.
- 5- The traffic signs and riprap have been removed from the outlet channel.

Site No. 11-A ✓ 249.14

- 1- The bushes and tree sprouts on the dam and in the emergency spillway have been pulled, cut or sprayed.
- 2- The roadway guardrail repair is to be completed by the Town and not by us.

A more complete report will follow indicating all the work accomplished this year with respect to this year's O & M maintenance field inspection reports.

Very truly yours,

George McGee Sr.
George M. McGee, Sr.,
Chairman

GME:GLK:paf

MAINTENANCE CHECKLIST FOR PL 566 FLOOD CONTROL STRUCTURES

This maintenance checklist is a guide for determining the maintenance required for Public Law 566 flood control structures in New Hampshire. It doesn't take the place of experience and judgment and is not inclusive. Items of a difficult nature to check, such as principal spillway conduit condition, are not included. Intensive checks of these items are necessary at proper intervals. Review of As Built drawings, the design folder, structure history, and previous maintenance reports should be part of the inspection. Prompt maintenance is a vital part of safe and effective operation.

Except where otherwise indicated, completion of this form may be facilitated by ranking maintenance items on a 1 to 4 basis where

- 1 = satisfactory
- 2 = satisfactory, but check carefully at next inspection
- 3 = requires maintenance this season
- 4 = requires immediate attention.

242.14

WATERSHED Baker SITE 11A DATE 6-13-78
 INSPECTED BY Garv Kerr, Lyall Milligan (WRB); Mike Dannehy, Nick Luhtala, Rav Wenninger
(SGS)

1. GENERAL ITEMS

Access Road.	N/A
Site Fencing.	N/A
Traffic Conditions.	1
Vandalism Control.	1
Trash Control.	1

COMMENTS _____

2. RESERVOIR

Timber stand at reservoir.	1
Debris and slash.	1
Sediment level in relation to low stage inlet	1

COMMENTS _____

3. EMBANKMENT AND EXCAVATED SLOPES

(Report riprap and vegetation and erosion condition under Items 4 and 5.)

	Dam	Dike	Emergency Spillways ^{1/}		Other	
			left	right	()	()
Sliding or sloughing	<u>1</u>	—	—	<u>1</u>	—	—
Holes (rodent and other) (check especially at embankments)	<u>1</u>	—	—	<u>1</u>	—	—
Excessive settlement (embankments)	<u>1</u>	—	—	<u>1</u>	—	—
Cracks						
Traverse	<u>1</u>	—	—	<u>1</u>	—	—
Longitudinal	<u>1</u>	—	—	<u>1</u>	—	—
Seepage <u>2/</u>	<u>1</u>	—	—	<u>1</u>	—	—
Piping <u>2/</u>	<u>1</u>	—	—	<u>1</u>	—	—

COMMENTS _____

4. RIPRAP

	Displ. of Rock	Loss of Spalls	Loss of Bedding	Erosion of Found.	Break- down of Rock
Dam					
Upstream berm	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>
Principal Spillway Outlet	<u>3</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>
Embankment Gutters					
left	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>
right	—	—	—	—	—
Emergency Spillway					
location _____	—	—	—	—	—
location _____	—	—	—	—	—
Waterways					
location _____	—	—	—	—	—
location _____	—	—	—	—	—
Outlet Channel	—	—	—	—	—
Other _____	—	—	—	—	—

COMMENTS A few stones at PS outlet should be moved from the pipe outlet
back to the side of the plunge pool.

^{1/}Looking downstream.

^{2/}Check especially at downstream face of embankments.

5. VEGETATION

	Dam	Emergency Spillways ^{1/}		Dike	Outlet Channel	Water way	Other ()
		left	right				
Condition of stand (including need for lime and fertilizer)	1	—	1	—	—	—	—
Undesirable vegetation	—	—	—	—	—	—	—
Drainage (surface)	—	—	—	—	—	—	—
Erosion ^{2/}	—	—	—	—	—	—	—
Sedimentation	—	—	—	—	—	—	—
Condition of planting	—	—	—	—	—	—	—
Pest control	—	—	—	—	—	—	—
Fire control	—	—	—	—	—	—	—

COMMENTS Emergency spillway - wet and aquatic vegetation coming in.

Vegetation looks good.

6. EMBANKMENT, STRUCTURAL, & OTHER DRAINS

		Dam ^{1/}		Other	
		left	right	()	()
Depth of Flow	With any obstruction	—	—	—	—
(in inches above invert)	Without any obstruction	none	none	—	—
Turbidity of Discharge	With any obstruction	—	—	—	—
(yes, no)	Without any obstruction	—	—	—	—
Condition of Protective	Outside	1	1	—	—
Coating	Inside	1	1	—	—
Obstruction in Flow		no	no	—	—
(yes, no)					
Animal Guard Condition		1	1	—	—
Outlet Condition		1	1	—	—
Retarding Pool Elevation (ft. msl)	_____ or 0.1 (ft.)	above below top of orifice			
Other	_____				

COMMENTS

^{1/}Looking downstream.^{2/}Including wave, surface, stream, manmade, and livestock erosion.

7. RISER

Caution Be extremely careful when using ladders. Check condition before using. Ladders are sometimes broken, loose, corroded, and or slippery.
Use safety harness.

Ladders:
inside and out

Condition of protective coating___;
Corrosion___; Damaged parts___; Loose___;
Other___.

Concrete:
~~inside and~~ out

Cracking 1; Spalling 1; Other deterioration 1; Excessive movement (check joint at riser and conduit)___; Other___.

Trashracks:
low and high stage

Condition of protective coatings 1; Corrosion 1; Damaged parts 1; Condition of fastenings___; Need of gratings due to beaver___; Safety condition (protruding fastenings, sharp edges, etc.)___; Other___.

Manhole:

Condition of protective coatings___; Corrosion___; Damage___; Lock operable___; Other___.

Gate:
including lifting device, stem, guides, disc

Condition of protective coating___; Corrosion___; Damaged parts___; Condition of fastenings___; Stem alignment___; Lubrication___; Operation___; Other___.

Safety Items:

Condition of warning signs___; Condition of safety equipment___; Other___.

COMMENTS Did not go down riser. Should check interior of riser, gate operation and conduit at suitable intervals.

IMPACT BASIN, SAF, BOX INLET, & MISCELLANEOUS CONCRETE STRUCTURES

(specify) _____

N/A

Concrete:
inside and out

Cracking___; Spalling___; Other deterioration___;
Excessive movement (check joints)___;
Waterstops___; Joint sealant___; Other___.

Trashracks:
low and high stage

Condition of protective coatings___; Corrosion___;
Damaged parts___; Condition of fastenings___;
Need of gratings due to beaver___; Safety condition (protruding fastenings, sharp edges, etc.)___; Other___.

Gates:
including lifting device, stem, guides, disc, flap

Condition of protective coating___; Corrosion___;
Damaged parts___; Condition of fastenings___;
Stem alignment___; Operation___; Lubrication___; Wood decay___; Other___.

Structure Drainage:

Report under "Embankment and Other Drains"

Structure, Railing, Grates, Barriers, etc.

Condition of protective coating___; Corrosion___;
Damaged parts___; Condition of Fastenings___;
Wood decay___; Safety condition (protruding fastenings, sharp edges, etc.)___; Other___.

Safety Items:

Condition of warning signs___; Condition of safety equipment___; Other___.

COMMENTS _____

CHANNEL

Stream obstructions.	2
Debris in stream.	1
Sediment bars controlled.	1
Plunge pool stability.	1
Fish habitat appurtenances	1
Riprap -- Report under "Riprap" (item 4)											

COMMENTS Little vegetation in outlet channel.

MAINTENANCE CHECKLIST FOR PL 566 FLOOD CONTROL STRUCTURES

This maintenance checklist is a guide for determining the maintenance required for Public Law 566 flood control structures in New Hampshire. It doesn't take the place of experience and judgment and is not inclusive. Items of a difficult nature to check, such as principal spillway conduit condition, are not included. Extensive checks of these items are necessary at proper intervals. Review of Built drawings, the design folder, structure history, and previous maintenance reports should be part of the inspection. Prompt maintenance is a vital part of safe and effective operation.

Except where otherwise indicated, completion of this form may be facilitated by ranking maintenance items on a 1 to 4 basis where

- 1 = satisfactory
2 = satisfactory, but check carefully at next inspection
3 = requires maintenance this season
4 = requires immediate attention.

WATERSHED BAKER RIVER SITE 11A DATE 5-20-77
INSPECTED BY KEP JOHNNIE LUHTALA
MILLIGAN KELSEY MACPHERSON

1. GENERAL ITEMS

[illegible]

COMMENTS GUARD RAIL POST BROKEN OFF - INLET
END OF E.M. SPILLWAY. TRAIN ON DAM

RESERVOIR[illegible]

COMMENTS BLOW DOWN & DEAD TREES IN RESERVOIR

2. EMBANKMENT AND EXCAVATED SLOPES

(Report riprap and vegetation and erosion condition under Items 4 and 5.)

	Dam	Dike	Emergency Spillways ^{1/}		Other	
			left	right	()	()
Sliding or sloughing	<u>1</u>	—	—	<u>1</u>	—	—
Holes (rodent and other) (check especially at embankments)	<u>3</u>	—	—	<u>1</u>	—	—
Excessive settlement (embankments)	<u>1</u>	—	—	<u>1</u>	—	—
Cracks						
Traverse	<u>1</u>	—	—	<u>1</u>	—	—
Longitudinal	<u>1</u>	—	—	<u>1</u>	—	—
Seepage ^{2/}	<u>1</u>	—	—	<u>1</u>	—	—
Piping ^{2/}	<u>1</u>	—	—	<u>1</u>	—	—

COMMENTS HOLE IN DOWNSTREAM FACE ON PR. SPILLWAY LINE.

4. RIPRAP

	Displ. of Rock	Loss of Spalls	Loss of Bedding	Erosion of Found.	Break- down of Rock
Dam					
Upstream berm	<u>1</u>	—	—	—	—
Principal Spillway Outlet	<u>3</u>	—	—	—	—
Embankment Gutters					
left	<u>1</u>	—	—	—	—
right	<u>1</u>	—	—	—	—
Emergency Spillway					
location	<u>1</u>	—	—	—	—
location	<u>1</u>	—	—	—	—
Waterways					
location	—	—	—	—	—
location	—	—	—	—	—
Outlet Channel	<u>1</u>	—	—	—	—
Other	—	—	—	—	—

COMMENTS REMOVE ROCKS IMMEDIATELY UNDER OUTLET
OF PR. SPILLWAY PIPE

^{1/}Looking downstream.

^{2/}Check especially at downstream face of embankments.

5. VEGETATION

	Dam	Emergency Spillways		Dike	Outlet Channel	Water way	Other ()
		left	right ^{1/}				
Condition of stand (including need for lime and fertilizer)	<u>1</u>	—	<u>1</u>	—	<u>NA</u>	—	—
Undesirable vegetation	<u>3</u>	—	<u>2</u>	—	<u>1</u>	—	—
Drainage (surface)	<u>NA</u>	—	<u>1</u>	—	<u>NA</u>	—	—
Erosion ^{2/}	<u>1</u>	—	<u>1</u>	—	<u>1</u>	—	—
Sedimentation	<u>1</u>	—	<u>1</u>	—	<u>1</u>	—	—
Condition of planting	<u>NA</u>	—	<u>NA</u>	—	<u>NA</u>	—	—
Pest control	—	—	—	—	—	—	—
Fire control	—	—	—	—	—	—	—

COMMENTS POPLARS GROWING ON DAM6. EMBANKMENT, STRUCTURAL, & OTHER DRAINS

		Dam		Other	
		left	right ^{1/}	()	()
Depth of Flow (in inches above invert)	With any obstruction	—	—	—	—
	Without any obstruction	<u>0</u>	<u>0</u>	—	—
Turbidity of Discharge (yes, no)	With any obstruction	—	—	—	—
	Without any obstruction	<u>NO</u>	<u>NO</u>	—	—
Condition of Protective Coating	Outside	<u>1</u>	<u>1</u>	—	—
	Inside	<u>1</u>	<u>1</u>	—	—
Obstruction in Flow (yes, no)		<u>NO</u>	<u>NO</u>	—	—
Animal Guard Condition		<u>1</u>	<u>1</u>	—	—
Outlet Condition		<u>1</u>	<u>1</u>	—	—
Retarding Pool Elevation (ft. msl) _____ or _____ (ft.) above _____ below _____					
Other _____					

COMMENTS _____

^{1/}Looking downstream.^{2/}Including: wave, surface, stream, manmade, and livestock erosion.

RISER

Caution Be extremely careful when using ladders. Check condition before using. Ladders are sometimes broken, loose, corroded, and or slippery. Use safety harness.

Ladders:
inside and out

Condition of protective coating____;
Corrosion____; Damaged parts____; Loose____;
Other_____.

Concrete:
inside and out

Cracking____; Spalling____; Other deterioration____;
Excessive movement (check joint at riser and conduit)____; Other_____.

Trashracks:
low and high stage

Condition of protective coatings____; Corrosion____;
Damaged parts____; Condition of fastenings____;
Need of gratings due to beaver____; Safety condition (protruding fastenings, sharp edges, etc.)____; Other_____.

Manhole:

Condition of protective coatings____; Corrosion____;
Damage____; Lock operable____; Other_____.

Gate:
including lifting device, stem, guides, disc

Condition of protective coating____; Corrosion____;
Damaged parts____; Condition of fastenings____;
Stem alignment____; Lubrication____; Operation____; Other_____.

Safety Items:

Condition of warning signs____; Condition of safety equipment____; Other_____.

COMMENTS WAB WILL CHECK RISER & APPURTENANCES
AT LATER DATE

IMPACT BASIN, SAF, BOX INLET, & MISCELLANEOUS CONCRETE STRUCTURES

(specify) CRADLE

Concrete: Cracking /; Spalling /; Other deterioration /;
inside and out Excessive movement (check joints) /;
Waterstops /; Joint sealant /; Other /.

Trashracks: Condition of protective coatings /; Corrosion /;
low and high stage Damaged parts /; Condition of fasten-
ings /; Need of gratings due to beaver /;
Safety condition (protruding fastenings, sharp
edges, etc.) /; Other /.

Gates: Condition of protective coating /; Corrosion /;
including lifting Damaged parts /; Condition of fasten-
device, stem, guides, ings /; Stem alignment /; Operation /;
disc, flap Lubrication /; Wood decay /; Other /.

Structure Drainage: Report under "Embankment and Other Drains"

Structure, Railing, Condition of protective coating /; Corrosion /;
Grates, Barriers, Damaged parts /; Condition of Fasten-
etc. ings /; Wood decay /; Safety condition
(protruding fastenings, sharp edges, etc.)
/; Other /.


Safety Items: Condition of warning signs /; Condition of
safety equipment /; Other /.

COMMENTS _____


9. CHANNEL

Stream obstructions.	3
Debris in stream.	1
Sediment bars controlled.	1
Plunge pool stability.	1
Fish habitat appurtenances	1
Riprap -- Report under "Riprap" (item 4)												


COMMENTS REMOVING "CAT-O-NINE TAILS" FROM CHANNEL




SECTION A-A



SECTION B-B



A



SECTION C-C

1. THE INFORMATION SHOWN ON THESE DRAWINGS IS BASED ON THE ORIGINAL CONSTRUCTION PLANS AND VISUAL OBSERVATIONS MADE DURING THE FIELD INSPECTION. DIMENSIONS OR MATERIALS INDICATED ON THESE DRAWINGS WHICH WERE BELOW GRADE OR WATER DURING THE TIME OF INSPECTION WERE NOT VERIFIED.

2. THE ELEVATIONS SHOWN ARE 1929 MSL DATUM.


ELEV 654.5'
ELEV 651.8'

2' THICK ROCK RIP RAP
ON 6" BEDDING

EARTH FILL REQUIREMENTS			
ZONE	MATERIAL	REQUIRED WATER CONTENT	COMPACTION DEFINITION
1	SILTY FINE TO MEDIUM FINE	-1% OF OPTIMUM TO +3% OF OPTIMUM	95% MAXIMUM DENSITY BY ASTM D698 METHOD A

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	
SITE NO. IIA	
BAKER FLOODWATER	
RESERVOIR	
WENTWORTH, N.H.	

Figure 2 of 2



LEGEND
 ▲ INDICATES LOCATION WHERE PHOTO WAS TAKEN AND DIRECTION

THE INFORMATION SHOWN ON THESE DRAWINGS IS BASED ON THE ORIGINAL CONSTRUCTION PLANS AND VISUAL OBSERVATIONS MADE IN 1960. THE FIELD INSPECTION, CONDUCTED IN 1960, INDICATED THAT THE MATERIALS USED IN THE CONSTRUCTION OF THE RESERVOIR WERE OF SATISFACTORY QUALITY. THE TIME OF INSPECTION WAS NOT VERIFIED.

NATIONAL BUREAU OF SURVEYING	
SITE NO. 11A	
BAKER FLOODWATER RESERVOIR	
DATE	1960
BY	W. B. BAKER
FOR	U. S. ARMY CORPS OF ENGINEERS

APPENDIX C

PHOTOGRAPHS

FOR LOCATION OF PHOTOS, SEE FIGURE 1
LOCATED IN APPENDIX B




PHOTO NO. 1 - View of reservoir area from dam.




PHOTO NO. 2 - View of upstream face of dam from right abutment.



PHOTO NO. 3 - View of downstream face of dam from right abutment.



PHOTO NO. 4 View of dam crest from right abutment.



PHOTO NO. 5 - View of dam crest from left abutment.



PHOTO NO. 6 - View of principal spillway and riser.

PHOTO NO. 7 - View of right side of principal spillway.



PHOTO NO. 8 - View of left side of principal spillway.



PHOTO NO. 9 - View of low stage intake trash rack.




PHOTO NO. 10 - View of high stage trash rack.



PHOTO NO. 11 - View of outlet works and discharge channel
from dam.



PHOTO NO. 12 - View of outlet works and foundation drain
pipes.




PHOTO NO. 13 - Close up view of discharge pipe.




PHOTO NO. 14 - Close-up view of discharge pipe support structure.




PHOTO NO. 15 - Upstream end of emergency spillway as seen from axis of dam.



PHOTO NO. 16 - Downstream end of emergency spillway as seen from axis of dam.

APPENDIX D
HYDROLOGIC AND HYDRAULIC COMPUTATIONS

HNTB HOWARD NEEDLES TAMMEN & BERGENDOFF	Made by	RY	Date	6/18/79	Job No	5965-11-08
	Checked by	HM	Date	7/2/79	Sheet No	1
For Baker River Dam #11A						

Hydraulics & Hydrology

Baker River Dam Site No. 11A: Located on a tributary to the Baker River in the Town of Wentworth, N.H. in the Merrimack River Basin.

Classification: Size Small
Hazard: High

Basic Data: Drainage Area: 1.05 sq mi
Upstream Basin: Mountainous 774 ft/mi

Reservoir: Normal Pool: elev-664.0
Stor. - 9 ac-ft
Emer. Spillway elev. 674.5
Stor. 238.0
Top of Dam elev 681.5
Stor. 355 ac-ft

Dam: Earth
Length 640 ft
Height 24 ft
Spillways Riser Crest 676.76 ft
Length of Crest 15 ft
Emer. Spillway Crest 678.5
Width 140 ft.

See Appendix B for Plan of Dam

HNTB HOWARD NEEDLES TAMMEN & BERGENDOFF	Made by	RY	Date	6/18/79	Job No.	5965-11-08
	Checked by	H!!	Date	7-1-79	Sheet No.	2
For Baker #11A						

Step 1 Calculation of Test Flood Inflow

Classification Size Small
Hazard High

Hydrologic Guideline Recommends

1/2 PMF to PMF

use 1/2 PMF as

Height 24 feet in mid-range of
classification range of 10 to 40 feet and
Hazard is on lower range of range - 4 dwellings affected.
Use Mountainous Curve PMF 3000 CSM (max
recommended value)

$$\text{Test Flood Inflow} = 3000 \text{ CSM} \times 1.05 \text{ mi}^2 \times \frac{1}{2} = 1580$$

As this is a flood control reservoir the portion of the
storage above the normal pool can be used to store
a portion of the PMF

Storage @

9 acre-ft normal pool
238 acre-ft @ crest of emergency spillway
229 acre-ft available for storage of PMF.

$$\text{Volume of } \frac{1}{2} \text{ PMF} = \frac{19}{12} \frac{\text{in}}{\text{ft}} \times 640 \frac{\text{acres}}{\text{mi}^2} \times 1.05 \text{ mi}^2 \times \frac{1}{2} = 532 \text{ acre-ft}$$

HNTB HOWARD NEEDLES TAMMEN & BERGENDOFF For <u>Baker #11A</u>	Made by <u>RY</u>	Date <u>6/18/79</u>	Job No. <u>5965-11-08</u>
	Checked by <u>HN</u>	Date <u>7/1/79</u>	Sheet No. <u>3</u>

Step 2 Calculation of F-Test F Surcharge

Stage-Discharge Curve

<u>Elev.</u>	<u>ft. above Emerg. Spillway</u>	<u>A Riser Pipe Flow</u>	<u>B Emergency Spillway</u>	<u>C Crest of Dam</u>	<u>Total</u>
678.5	0	98			98
679.33	.83	99	100		199
679.95	1.45	101	300		401
680.5	2.08	102	600		702
681.08	2.50	104	900		1004
681.14	2.64	104	1000		1104
682.28	3.78	107	2000	1362	3469
683.18	4.68	109	3000	4307	7416

A. From Baker River Dam #11A Design Book, SCS, Durham, N.H. See copies of the Calcs. at the end of this section.

B. Same As "A"

C. Computed as flow over a broadcrested weir crest of Dam at 681.5

$$Q = CLH^{3/2}$$

$$C = 3.09$$

$$L = 640 \text{ ft}$$

$$Q = 1978 H^{3/2}$$

$$\begin{array}{r} \text{Ht top of dam} \\ 1169 \\ 105 \\ \hline 1274 \end{array}$$

See fig 2 for plot

HNTB HOWARD NEEDLES TAMMEN & BERGENDOFF	Made by	RY	Date	6/19/79	Job No.	5965-11-08
	Checked by	HJ	Date	7/1/79	Sheet No.	4
For Baker #11A						

Step 3 Estimate of Surge - Storage Effect

$$Q_{P1} = 1580 \text{ cfs}$$

$$\text{Runoff} = 9.5 \text{ inches}$$

$$Q_{P2} = Q_{P1} \times \left(1 - \frac{\text{Stor}}{9.5}\right)$$

Stor in acre-ft read from Figure 1 - 9.0 acre-ft

$$\text{Stor (in)} = \frac{\text{Stor acre-ft} \times 12 \text{ in/ft}}{1.05 \text{ mi}^2 \times 640 \text{ acre/mi}^2} = .0179 (\text{Stor}_{\text{acre-ft}})$$

<u>Clev.</u>	<u>Stor (acre-ft)</u>	<u>Stor (in)</u>	<u>Q_{P2}</u>
680	285	5.10	731 $\frac{\text{cfs}}{\text{ft}}$
681	326	5.84	609
682	366	6.55	490
683	408	7.30	365


See Figure 2 for Plot and Final outflow

From Figure 2 Outflow 670 $\frac{\text{cfs}}{\text{ft}}$

Stage 2.0 ft above spillway crest

elev. 680.5

Freeboard = 1.0 ft.



11-2-10-1




Fig. 10

HNTB HOWARD NEEDLES TAMMEN & BERGENDOFF For <u>Baker #11A</u>	Made by <u>RY</u>	Date <u>5/25/79</u>	Job No. <u>5965-11-08</u>
	Checked by <u>HJ</u>	Date <u>7/19/79</u>	Sheet No. <u>5</u>

Estimate of Downstream Damage

Step 1 Reservoir Storage

at top of dam - Elev. 681.5 ft
Storage. 355 acre-ft.

Step 2 Breach Outflow

$$Q_{\text{Breach}} = 8/27 \sqrt{g} W_0 Y_0^{3/2}$$

$W_0 = 40\%$ of the total length of dam


$Y_0 = \text{height-stream bed to max pool elevation. } 24 \text{ ft}$

$$\text{Breach Outflow } 8/27 (5.67 \times .40 \times 640 \times 24)^{3/2} = 50,600 \text{ cfs}$$

1274

Say $Q_{P1} = 51,940 \text{ cfs}$

Step 3 Downstream Stage-Discharge



Reach Length = 6000 ft.

$$S_{\text{channel}} = .02 \frac{1}{4}$$

$$n_{\text{ch}} = .04$$

$$n_{\text{OB}} = .08$$

Stage - Discharge

5 ft	1320 cfs
7	3000
9	5690
12	12,090
15	21,870
18	35,620
21	53,870

HNTB

Made by

RY

Date

5/24/79

Job No

5965-11-08

Checked by

HAI

Date

7-10-79

Sheet No

6

HOWARD NEEDLES TAMMEN & BERGENDOFF

For Baker #11A

Step 4 Downstream Stage $S = 355 \text{ acre ft}$ $Q_{p1} = 51,900 \text{ cfs}$ Length 6000 ftStage 1, 20.8 ft area₁ = 3600 ft²

$$V_1 = \frac{3600 \text{ ft}^2 \times 1900 \text{ ft}}{43560 \text{ ft}^2/\text{acre}} = 157 \text{ acre-ft} \leq \frac{355}{2}$$

Reach length OK

$$Q_{p2 \text{ trial}} = 51,900 \left(1 - \frac{157}{355}\right) = 28,950 \text{ cfs}$$

Stage 2 = 16.7 ft area₂ = 2226 ft²

$$V_2 = \frac{2226 \times 1900}{43560} = 97 \text{ acre-ft}$$

 $V_{\text{ave}} = 127 \text{ acre-ft}$

$$Q_{p2} = 51,900 \left(1 - \frac{127}{355}\right) = 33,330 \text{ cfs}$$

Stage 1 = 17.6 ft area₁ = 2500 ft²

$$V_1 = \frac{2500 \times 2000}{43560} = 115 \text{ acre-ft}$$

$$Q_{p2 \text{ trial}} = 33,330 \left(1 - \frac{115}{355}\right) = 22,550 \text{ cfs}$$

Stage 2 = 15.2 ft area₂ = 1805 ft²

$$V_2 = \frac{1805 \times 2000}{43560} = 83 \text{ acre-ft}$$

 $V_{\text{ave}} = 99 \text{ acre-ft}$

$$Q_{p2} = 33,330 \left(1 - \frac{99}{355}\right) = 24,030 \text{ cfs}$$

Stage = 15.6 ft

1A
1900 ft x
6000 ft1B
2000 ft x
6000 ft

HNTB

HOWARD NEEDLES TAMMEN & BERGENDOFF

For Baker # 11A

Made by

RY

Date

5/24/79

Job No.

5965-11-08

Checked by

HM

Date

7/19/79

Sheet No

7

$$Q_{P_1} = 24,100 \text{ cfs}$$

$$\text{Stage}_1 = 15.6 \text{ ft} \quad \text{area}_1 = 1913 \text{ ft}^2$$

$$V_1 = \frac{1913 \times 2100}{43560} = 92.0 \text{ acre-ft}$$

$$Q_{P_2 \text{ trial}} = 24,030 \left(1 - \frac{92}{355}\right) = 17,800 \text{ cfs}$$

$$\text{Stage}_2 = 13.9 \text{ ft} \quad \text{area}_2 = 1475 \text{ acre-ft}$$

$$V_2 = \frac{1475 \times 2100}{43560} = 71.0 \text{ acre-ft}$$


$$V_{ave} = 81.5 \text{ acre-ft}$$

$$Q_{P_2} = 24,030 \left(1 - \frac{81.5}{355}\right) = 18,500 \text{ cfs}$$


$$\text{Stage} = 14.1 \text{ ft}$$


Summary

R reach	Stage
At Dam	20.7 ft
Near Buffalo Rd u.s. side	17.6 ft
1000 ft ds. of Buffalo Rd.	15.5 ft
At confluence w/ Baker River 6000 ft ds.	14.1 ft



Stacy Drainage
Curve
Trib to Baker River
Baker Drainage
5965-11-34





BAKER RIVER DAM
SITE 11A

POSSIBLE FLOOD DAMAGE
AREA DUE TO DAM FAILURE

NATIONAL PROGRAM OF INSPECTION OF NON FEDERAL DAMS	
BAKER RIVER DAM SITE 11A POSSIBLE FLOOD DAMAGE AREA	
Wentworth, N.H. USGS Quad	Scale 1:24,000 FEET 1000

SITE HA - SACER RD CR W/4

...and By ...

فقد و استمر

1900

ITEM	UNIT	WATER	SEWER	REMARKS
DRAINAGE AREA	SQ MI.	1.05	1.05	
SYN. CAP. CAPACITY				
SEW. INLET (H/O ADJUSTED)	FOOT	13	13	
MAN. RIGAL	FOOT	0	0	
RETARDING	FOOT	205	225	BASED ON 5% SLOPE
TOTAL	FOOT	220	235	
DETERMINED BY LOW S	FOOT	134	170	BASED ON 5% SLOPE TO CENTRAL FLOW
SURFACE AREA				
LOT TOTAL AREA	SQ. FT.	2	2.05	ADDED DETAIL 2.05
RETARDING AREA	SQ. FT.			
DESIGN HIGH WATER	FOOT	32	33.0	
VOLUME OF DRAIN	CUB. YD.	15,347	33,7	
TIME TO DRAIN	FEET	131.0	137	
EMERGENCY SPILLWAY	FEET	22	20.2	
DETERMINED BY	FEET	270.2	270.2	BASED ON 5% SLOPE
DETERMINED BY	FEET	22	22.2	
TIME		24.74	24.74	
PERCENT CHANGE OF USE		1	1	
ADJUSTED TO 20 IN. II		23	23	
EMERGENCY SPILLWAY				
DETERMINED BY R.	IN	7	7	
DETERMINED BY	IN	3.44	3.44	
VOLUME OF FLOW - V	CFS			
PEAK DISCHARGE RATE	CFS			
PEAK WATER SURFACE EL.	FEET	270.2	270.2	
DETERMINED BY SPILLWAY				
SEW. DRAINAGE - 5 HR	IN.	10.5	10.5	
SEW. RUNOFF	IN.	5.26	5.26	
VOLUME OF FLOW - V	CFS	5.5	1.55	
PEAK DISCHARGE RATE	CFS	6.12	5.27	
PEAK WATER SURFACE EL.	FEET	251.2	250.12	
PROPOSED SPILLWAY				
RIDGE SIZE	FT.	25.2x7.52	25.2x7.52	
MAX. LOW STAGE FLOW	CFS	1.5	1.0	
ORIFICE SIZE	FT.	0.165x2.55	0.165x1.7	
MAX. HIGH STAGE FLOW	CFS	7.4	1.77	
PIPE SIZE	DIA	30.11	30.11	
CAPACITY EQUIVALENTS				
TOTAL SEDIMENT VOL.	IN	1.25	1.25	
REGARDING STORAGE	IN	3.7	3.25	
EM. SPILLWAY STORAGE				
TO TOP OF DAM	IN	1.12	1.25	
CLASS OF STRUCTURE		5	5	
CONSTRUCTION COSTS				
R-C RATIO				

2055

SITE 111 - 34th Street NW, Wash DC

STATE OF ALABAMA

Q OF ENO AT 21 1 22

[illegible]

5

✓

1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1472	1473	1474	1475	1476	1477	1478	1479	1480	1481	1482	1483	1484	1485	1486	1487	1488	1489	1490	1491	1492	1493	1494	1495	1496	1497	1498	1499	1500
------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------

RECEIVED OCTOBER 16 AM 1987

STATE <u>N.H.</u>	PROJECT <u>SITE II A - BURNHAM RD 1/3</u>
BY <u>L. J. P.</u>	CHECKED BY <u>DATE</u>
DATE <u>2-19-69</u>	JOB NO <u>NH 515</u>
SUBJECT <u>ELEV OF EMERGENCY SPILLWAY CREST</u>	
<u>8 PERIOD NEAR F50</u>	
SHEET <u>15</u> OF <u>15</u>	

SUBMERGED SEDIMENT	125 ACFT
ACCRETED SEDIMENT	5,147 ACFT
214 IN. OF RUNOFF - LOW STAGE STORAGE	154,400 ACFT
113 IN. OF RUNOFF - HIGH STAGE STORAGE	11,000 ACFT
TOTAL STORAGE TO CREST OF EMERGENCY SPILLWAY	220,172 ACFT
FROM STAGE STORAGE CURVE 520,122 ACFT @	
STORAGE AT ELEV. 678.00	

THE TOTAL RUNOFF OF 310 INCHES IS STORED AS FLOOD STORAGE BETWEEN THE LOW STAGE ORIFICE CREST (ELEV. 674.0) AND ELEV. 675.00, THE REQUIRED CREST ELEVATION OF THE EMERGENCY SPILLWAY.

THE CREST OF THE EMERGENCY SPILLWAY WAS RISEN 1.00 FT TO STOP THE EMERGENCY SPILLWAY HYDROGRAPH IS REQUIRED BY THE WORKPLAN. THIS ALSO PROVIDED FOR SOME OF THE HIGH STAGE STORAGE LOST BY RAISING THE HIGH STAGE CREST. REQUIRED CREST ELEV. 678.00

SITE 11.0 - BAKER INFER WATERSHED

LOW STAGE DISCHARGE

2 OF COM AT 2 + 50

ELEV	STAGE	LOW STAGE MEIR $Q = 3.62 H^{5/2}_{LW}$			LOW STAGE CR. FILE $Q = 3.14 H^{5/2}_{LW}$			
		H_{LW}	$3/2 H_{LW}$	Q_{LW}	H_{LW}	$H^{5/2}_{LW}$	Q_{LW}	
664.0	0	0	0	0				
664.10	0.10	0.10	0.0315	0.11				0
664.25	0.25	0.25	0.1250	0.45	0	0	0	0
664.40	0.40	0.40	0.2530	0.72	0.15	0.3875	1.20	0
664.50	0.50	0.50	0.3536	1.05	0.25	0.5000	1.57	1
664.60	0.60	0.60	0.4648	1.35	0.35	0.5915	1.86	1
664.65	0.65	0.65	0.5367	1.63	0.43	0.6557	2.06	1
664.67	0.67	0.67	0.5732	1.67	0.44	0.6637	2.08	1
664.70	0.70	0.70	0.5557	2.12	0.45	0.6705	2.11	1
664.75	0.75	0.75	0.7158	2.59	0.55	0.7416	2.23	1
665.00	1.00	1.00	1.00	3.12	0.75	0.8660	2.72	1
665.50	1.50				1.25	1.1190	3.51	1
666.00	2.00				1.75	1.3220	4.15	1
667.00	3.00				2.75	1.6550	5.21	1
668.00	4.00				3.75	1.9365	6.08	1
669.00	5.00				4.75	2.1794	6.84	1
670.00	6.00				5.75	2.3979	7.53	1
671.00	7.00				6.75	2.5951	8.16	1
672.00	8.00				7.75	2.7837	8.74	1
673.00	9.00				8.75	2.9580	9.29	1
674.00	10.00				9.75	3.1225	9.80	1
675.00	11.00				10.75	3.2787	10.30	1
676.00	12.00				11.75	3.3941	10.83	1
676.25	12.25				11.75	3.4255	10.96	1
676.50	12.50				12.00	3.4641	11.15	1
676.75	12.75				12.25	3.4775	11.29	1
676.90	12.90				12.15	3.4551	11.24	1
677.00	13.00				12.25	3.4641	11.28	1

4 OF 200 DT 13-50

[illegible]

8.75 No

BAKER RIVER WATERSHED

EMERGENCY SPILLRY COMPUTATION:

$$h = 144' \quad L = 575' \quad n = 0.04' = 4:1 \text{ FLEW 679}$$

4-2-2020

[illegible]

SITE 11A @ DAM #150 ENL SPURWAY

NH 685

U. S. GOVERNMENT PRINTING OFFICE: 1969 O - 44700

NH-668

HYDROGRAPH COMPUTATION
EMERGENCY SPILLWAY HYDROGRAPH

WATERSHED OR PROJECT BAKER RIVER STATE N.H.

STRUCTURE SITE OR SUBAREA SITE 11.9

DR. AREA 1.05 SQ. MI. T_c 1.8 HR. RUNOFF CONDITION NO. II

RUNOFF CURVE NO. 68 STORM DISTRIB. CURVE B HYDROGRAPH FAMILY NO. 3

STORM DURATION 6 HR. RAINFALL: POINT 7.0 IN. AREAL 6.66 IN.

Q 3.14 IN. $T_H = 0.7 T_c$ COMPUTED T_p 1.26 HR. T_o 4.45 HR.

$(T_o + T_p)$: COMPUTED 3.53 : USED 4.0 REVISED T_p 1.11

$q_p = \frac{484 A}{REV. T_p} = \frac{484 \times 1.05}{1.11} = 457.24$ CFS. $Q_{qp} = 1037.62$ CFS.

q (COLUMN) = $(t/T_p) REV. T_p$. q (COLUMN) = $(q_c/q_p) Q_{qp}$.

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS
1	6.00	0.00	21	7.99	8.63	41		
2	0.40	5.31	22	8.39	5.75	42		
3	0.80	63.26	23	8.79	2.00	43		
4	1.20	291.26	24	9.19	1.42	44		
5	1.60	575.05	25	9.59	0.00	45		
6	2.00	627.18	26			46		
7	2.40	646.73	27			47		
8	2.80	510.74	28			48		
9	3.20	491.67	29			49		
10	3.60	425.54	30			50		
11	4.00	319.47	31			51		
12	4.40	336.40	32			52		
13	4.80	301.90	33			53		
14	5.19	242.46	34			54		
15	5.59	159.56	35			55		
16	5.99	96.32	36			56		
17	6.39	53.19	37			57		
18	6.79	31.63	38			58		
19	7.19	20.13	39			59		
20	7.59	11.50						

$\Sigma q = 5,398.74$

$Q = \frac{\Sigma q}{\Delta t} = \frac{5,398.74}{6.66} = 809.12$

$Q = 809.12$

$Q = 0.40 \times 5,398.74$

647.91×1.05

$Q = 680.31$

$Q = 680.31$

$Q = 3.19$

$100 \times \frac{0.05}{3.19} = 1.59\%$

17142
11-29-6
NH-688
V DPP
12-1-6

HYDROGRAPH COMPUTATION

FLOODING HYDROGRAPH

WATERSHED OR PROJECT RAVINE RIVER STATE N.H.STRUCTURE SITE OR SUBAREA SITE 11ADR. AREA 1.05 SQ. MI. T_c 1.8 HR.RUNOFF CONDITION NO. IIRUNOFF CURVE NO. 63 STORM DISTRIB. CURVE B HYDROGRAPH FAMILY NO. 3STORM DURATION 6 HR.

RAINFALL:

POINT 10.5 IN.AREAL 10.0 IN. Q 5.76 IN. $T_p = 0.7 T_c$
COMPUTED T_p 1.26 HR. T_o 4.87 HR. $(T_o + T_p)$ COMPUTED 3.87 :USED 4.0 .REVISED T_p 1.22 . $q_p = \frac{Q A}{K O F T_p} = \frac{5.76 \times 10.0}{1.22} = 46.56$ CFS. $Q q_p = \frac{2,485.70}{1} = 2,485.70$ CFS. $t(\text{COLUMN}) = (1/T_p) \text{ REV. } T_p$ $q(\text{COLUMN}) = (q_c/q_p) Q q_p$

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS
1	0.00	0.00	21	8.78	14.90	41		
2	0.44	7.45	22	9.22	9.93	42		
3	0.88	127.86	23	9.66	4.97	43		
4	1.32	503.98	24	10.10	2.48	44		
5	1.76	973.09	25	10.54	0.00	45		
6	2.20	1,117.22	26			46		
7	2.64	1,117.22	27			47		
8	3.07	973.09	28			48		
9	3.51	842.09	29			49		
10	3.95	732.01	30	$\Sigma Q = 9,322.55$		50		
11	4.39	632.05	31	$Q = 45 (39)$		51		
12	4.83	532.05	32	$64.5 A$		52		
13	5.27	532.05	33	$0.44 \times 9,322.55$		53		
14	5.71	412.58	34	64.5×1.05		54		
15	6.15	532.05	35	$4,101.92$		55		
16	6.59	167.36	36	671.25		56		
17	7.03	34.86	37	$Q = 6.06$		57		
18	7.47	54.43	38			58		
19	7.91	34.86	39	$100 \times \frac{9.10}{532} = 1.68\%$		59		

APRIL 1964

DATE VEILING; AREA HYDROGRAPH

[illegible]

PRINCIPAL SPILLWAY ROUTING

SITE 5
BAKER RIVER WATERSHED 11A

APRIL 1969

24 HOUR 26 HOURS
CURVE NO. 68., RAINFALL 5.78, 2 2.45 ** CURVE NO. 49., RAINFALL 10.40, 9 3.78
TC 1.00 LENGTH OF PIPE 110. MANNING'S 'N' VALUE 0.012 DRAINAGE AREA 1.05
BASE FLOW IS 1.00 CSM (1.00 CFS).

DISCHARGE TABLE GIVEN.

CONDUIT SIZE IS 30. INCHES.

ELEVATION	STORAGE	CFS
664.00	0.00	0.00
665.00	0.00	0.00
666.00	0.00	0.00
667.00	0.00	0.00
668.00	0.00	0.00
669.00	0.00	0.00
670.00	0.00	0.00
671.00	0.00	0.00
672.00	0.00	0.00
673.00	0.00	0.00
674.00	0.00	0.00
675.00	0.00	0.00
676.00	0.00	0.00
677.00	0.00	0.00
678.00	0.00	0.00
679.00	0.00	0.00
680.00	0.00	0.00
681.00	0.00	0.00
682.00	0.00	0.00
683.00	0.00	0.00
684.00	0.00	0.00
685.00	0.00	0.00
686.00	0.00	0.00
687.00	0.00	0.00
688.00	0.00	0.00
689.00	0.00	0.00
690.00	0.00	0.00
691.00	0.00	0.00
692.00	0.00	0.00
693.00	0.00	0.00
694.00	0.00	0.00
695.00	0.00	0.00
696.00	0.00	0.00
697.00	0.00	0.00
698.00	0.00	0.00
699.00	0.00	0.00
700.00	0.00	0.00

SITE 5
BAKER RIVER WATERSHED 11A

PRINCIPAL SPILLWAY ROUTING

APRIL 1967

CONDUIT DIAFTER IS 30. INCHES.

TIME	INFLOW	AVE IN	OUTFLOW	ELEV.	STORAGE
6.00	3.	3.	0.	664.43	1.0
12.00	3.	3.	1.	664.81	2.0
18.00	3.	3.	2.	665.01	2.7
24.00	3.	3.	2.	665.21	3.2
30.00	3.	3.	2.	665.43	3.5
36.00	3.	3.	3.	665.56	3.9
42.00	3.	3.	3.	665.67	4.1
48.00	4.	4.	3.	665.77	4.4
54.00	4.	4.	3.	665.87	4.5
60.00	4.	4.	3.	665.96	4.6
66.00	4.	4.	4.	666.02	4.7
72.00	5.	5.	4.	666.07	4.7
78.00	5.	5.	4.	666.16	4.8
84.00	6.	6.	4.	666.23	4.8
90.00	7.	7.	4.	666.35	5.4
96.00	8.	8.	4.	666.52	10.0
102.00	9.	9.	4.	666.73	12.3
108.00	13.	12.	4.	667.09	15.5
114.00	28.	15.	5.	667.53	21.1
120.00	32.9	19.5	10.	667.51	37.7
126.00	29.	19.	10.	667.40	13.1
132.00	15.	11.	10.	667.33	13.5
138.00	11.	11.	10.	667.38	14.5
144.00	10.	10.	10.	667.43	15.5
150.00	1.	1.	10.	667.59	12.3
156.00	1.	1.	9.	667.52	10.7
162.00	1.	1.	9.	667.40	9.7
168.00	1.	1.	9.	667.35	7.3
174.00	1.	1.	8.	667.25	5.8
180.00	1.	1.	7.	667.31	4.4
186.00	1.	1.	5.	667.70	3.1
192.00	1.	1.	5.	667.72	2.8
198.00	1.	1.	4.	666.89	13.6
204.00	1.	1.	4.	666.29	6.9

PEAK

120.00

10.

667.43

15.5

10.7

9.7

7.3

5.8

4.4

3.1

2.8

13.6

6.9

MAXIMUM STORAGE IS 140.5 ACRE FEET (2.510 INCHES) AT ELEV. 675.38 (GUEST, EVER. SPA.1).

NET DETENTION STORAGE REQUIRED IS 140.5 ACRE FEET (2.510 INCHES).

GROSS STORAGE REMAINING AFTER 10 DAYS IS 6.9 ACRE FEET (0.124 INCHES) AT ELEV. 666.20 (START EMER. SPW. AND FREEBOARD ROUTINGS).

NET REMAINING STORAGE IS 6.9 ACRE FEET (0.124 INCHES).

77 PAUSE

6.9 X 100 = 4.9 9/10 REMAINING
140.5 74.196 REMAINING
C.S. 100% IN 140.5 FEET
C.S. 100% IN 140.5 FEET

3/17/51

E. S. DESIGN AND FREEDARD ROUTINGS.

BAKER RIVER IIA

JAS

M M

CURVE NO. 68. TC 1.80 STORM DURATION 6.00

EMER. SPH. RAINFALL 6.65 FREEDARD RAINFALL 10.00

CASE NO. 0. DRAINAGE AREA 1.05 EMER. SPP. CREST 678.5

801 140. LI 373. R02 0. L2 0. B03 0. L3 0.

ELEVATION	STORAGE	CFS	CFS	CFS
672.00	53.	9.	0.	0.
674.00	102.	10.	0.	0.
676.76	172.	11.	0.	0.
576.09	207.	7.	0.	0.
678.01	207.	6.	0.	0.
679.80	222.	9.	0.	0.
679.00	241.	13.	0.	0.
679.10	260.	350.	0.	0.
680.70	287.	520.	0.	0.
690.50	297.	600.	0.	0.
741.10	317.	927.	0.	0.

BAKER RIVER 11A

JAS

M 4

EMER. SPN. INTERVENING HYDROGRAPH.

TIME	0.00	0.25	0.50	0.75	1.00	1.25	1.50	1.75	2.00	2.25
0.00 +	0.	0.	0.	0.	0.	0.	0.	1.	16.	42.
2.50 +	114.	247.	410.	544.	625.	648.	526.	587.	547.	507.
5.00 +	467.	428.	396.	370.	347.	323.	293.	251.	205.	158.
7.50 +	121.	89.	65.	49.	35.	25.	18.	13.	7.	5.
10.00 +	4.	3.	2.	1.	0.	0.	0.	0.	0.	0.

EMER. SPILLWAY DESIGN ROUTING.

BAKER RIVER 11A

JAS

M M

80 = 140. L = 373.

TIME	INFLOW	AVE IN	OUTFLOW	ELFV.
0.25	0.	0.	0.	671.99
0.50	0.	0.	0.	671.99
0.75	0.	0.	0.	671.99
1.00	0.	0.	0.	671.99
1.25	0.	0.	0.	671.99
1.50	0.	0.	0.	671.99
1.75	1.	0.	0.	671.99
2.00	10.	5.	9.	672.00
2.25	42.	26.	9.	672.81
2.50	114.	77.	3.	673.39
2.75	247.	181.	9.	674.21
3.00	410.	329.	9.	674.81
3.25	548.	477.	9.	675.10
3.50	625.	565.	9.	675.71
3.75	648.	636.	10.	676.29
4.00	626.	637.	10.	676.80
4.25	537.	623.	10.	676.29
4.50	567.	567.	10.	675.74
4.75	475.	475.	10.	675.16
5.00	457.	487.	10.	675.55
5.25	428.	447.	17.	676.89
5.50	396.	412.	32.	677.17
5.75	370.	392.	46.	677.42
6.00	347.	369.	57.	677.65
6.25	323.	335.	59.	677.82
6.50	298.	308.	95.	678.02
6.75	231.	272.	95.	678.16
7.00	233.	272.	95.	678.23
7.25	165.	187.	95.	678.29
7.50	121.	141.	95.	678.32
7.75	89.	107.	95.	678.33
8.00	69.	77.	96.	678.31
8.25	48.	57.	96.	678.29
8.50	35.	42.	95.	678.25
8.75	26.	30.	95.	678.21
9.00	18.	22.	95.	678.16
9.25	13.	16.	95.	678.10
9.50	9.	11.	95.	678.04
9.75	6.	8.	75.	677.99
10.00	4.	5.	72.	677.94
10.25	3.	4.	70.	677.89
10.50	2.	2.	67.	677.84
10.75	1.	1.	65.	677.79
11.00	0.	1.	52.	677.76
11.25	0.	0.	50.	677.70
11.50	0.	0.	58.	677.66
11.75	0.	0.	56.	677.61
12.00	0.	0.	53.	677.57

PEAK

678.33

678.31

678.29

678.25

678.21

678.16

678.10

678.04

677.99

677.94

677.89

677.84

677.79

677.76

677.70

677.66

677.61

677.57

NO EMERGENCY SPILLWAY FLOW. NO FURTHER ROUTINGS MADE.

ROUTING OF SPILLWAY FLOW
FOR 100 YEAR FLOOD
AT BAKER RIVER 11A
JANUARY 1965
BY JAS
CHECKED BY JAS
APPROVED BY JAS

EMER. SPILLWAY FLOW
FOR 100 YEAR FLOOD
AT BAKER RIVER 11A
JANUARY 1965
BY JAS
CHECKED BY JAS
APPROVED BY JAS

BAKER RIVER 11A

JAS

M M

FREEBOARD INTERVALLING HYDROGRAPH.

TIME	0.00	0.25	0.50	0.75	1.00	1.25	1.50	1.75	2.00	2.25
0.00 +	0.	0.	0.	0.	0.	0.	1.	10.	44.	131.
2.50 +	301.	584.	899.	1140.	1267.	1276.	1206.	1109.	1017.	929.
5.00 +	844.	764.	700.	644.	604.	553.	502.	429.	349.	273.
7.50 +	206.	152.	111.	81.	59.	43.	31.	22.	16.	11.
10.00 +	8.	5.	3.	2.	1.	0.	0.	0.	0.	0.

AD-A156 533

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
BAKER FLOODWATER RESE. (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV JUL 79

2/2


UNCLASSIFIED

F/G 13/13 NL

END

FORMED

DATE



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

FREEBOARD ROUTING.

BAKER RIVER 11A

JAS

M 1

80 = 140. L = 373.

TIME	INFLOW	AVE IN	OUTFLOW	ELEV.
0.25	0.	0.	0.	671.99
0.50	0.	0.	0.	671.99
0.75	0.	0.	0.	671.99
1.00	0.	0.	0.	671.99
1.25	0.	0.	0.	671.99
1.50	1.	6.	1.	671.99
1.75	10.	6.	7.	672.00
2.00	44.	27.	9.	672.02
2.25	131.	84.	9.	672.10
2.50	301.	216.	9.	672.12
2.75	584.	443.	9.	672.78
3.00	893.	741.	9.	673.56
3.25	1150.	1019.	10.	674.43
3.50	1267.	1203.	10.	674.45
3.75	1376.	1372.	10.	674.49
4.00	1463.	1541.	44.	677.40
4.25	1539.	1738.	95.	678.18
4.50	1617.	1903.	137.	678.76
4.75	1694.	2073.	240.	679.18
5.00	1764.	2247.	352.	679.50
5.25	1830.	2416.	499.	680.08
5.50	1893.	2581.	509.	680.12
5.75	1954.	2742.	512.	680.13
6.00	2012.	2899.	506.	680.13
6.25	2068.	3054.	491.	680.13
6.50	2122.	3207.	468.	679.96
6.75	2174.	3358.	434.	679.71
7.00	2224.	3507.	405.	679.47
7.25	2272.	3654.	370.	679.44
7.50	2318.	3799.	330.	679.44
7.75	2362.	3942.	284.	679.31
8.00	2404.	4083.	243.	679.19
8.25	2444.	4222.	207.	679.09
8.50	2482.	4359.	176.	679.00
8.75	2518.	4494.	162.	678.92
9.00	2552.	4627.	150.	678.85
9.25	2584.	4759.	139.	678.77
9.50	2614.	4889.	128.	678.70
9.75	2642.	5017.	119.	678.64
10.00	2668.	5144.	109.	678.58
10.25	2692.	5269.	101.	678.52
10.50	2714.	5392.	96.	678.46
10.75	2734.	5513.	96.	678.40
11.00	2752.	5632.	96.	678.33
11.25	2768.	5749.	96.	678.27
11.50	2782.	5864.		
11.75	2794.	5977.		
12.00	2804.	6088.		

PEAK

VOLUME CHECK AT HP IS 0.03 PERCENT.
COMPUTED HP 1.63

77 PAUSE

SEE NOTES ON DRAWINGS
FIGURE 1-10-10
DATA

APPENDIX E

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS



INVENTORY OF DAMS IN THE UNITED STATES

PROJECT NUMBER	STATE COUNTY DIST	NAME	REPORT DATE
NH 247 NED	NH 009 02	BAKER FLOODWATER RESERVOIR SITE 11A	DAY MO YR 27 JUL 79

POPULAR NAME	NAME OF IMPONDMENT
	BAKER FLOODWATER RESERVOIR SITE 11A

RECORDS	RIVER OR STREAM	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	DIST FROM DAM (MI.)	POPULATION
01 05	TRIBUTARY BAKER RIVER	WENTNORTH	0	376

TYPE OF DAM	YEAR COMPLETED	PURPOSE	HYDRAULIC POWER CAPACITY (KW)	IMPOUNDING CAPACITIES (ACFT)	DIST OWN	FED R	PRV/FED	SCS A	VER/DATE
ALPG	1971	C	35	24	355				

REMARKS

DIS/ HAS	SPILLWAY	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CY)	POWER CAPACITY (KW)	NAVIGATION LOCKS
1	640 U 180	1275	38497		

OWNER	ENGINEERING BY	CONSTRUCTION BY
N H WAYER RESOURCES BD	SOIL CONSERVATION SER	ROBIE CONSTRUCTION CO

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
HOWARD NEEDLES TAMMEN BERGENDOFF	DAY MO YR 16 MAY 79	PL 92-367

REMARKS
33-SPILLWAY AND RISER

END

FILMED

8-85

DTIC